subbase

Material Table			
Station	Area	Volume	Cumulative Volume
0+000.00	2.48	0.00	0.00
0+020.00	2.48	49.63	49.63
0+040.00	2.48	49.63	99.27
0+060.00	2.48	49.63	148.90
0+080.00	2.48	49.63	198.53
0+100.00	2.48	49.63	248.17
0+120.00	2.48	49.63	297.80
0+140.00	2.48	49.63	347.43
0+160.00	2.48	49.63	397.07
0+162.82	2.48	7.01	404.07
0+170.00	2.48	17.81	421.88
0+174.82	2.48	11.96	433.84
0+180.00	2.48	12.85	446.70
0+186.82	2.48	16.92	463.62
0+190.00	2.48	7.89	471.52
0+200.00	2.18	23.19	494.70
0+202.82	2.18	6.07	500.78
0+210.00	2.18	15.44	516.22
0+220.00	2.18	21.55	537.77
0+222.82	2.18	6.08	543.85
0+230.00	2.18	15.50	559.35
0+240.00	2.18	21.61	580.96
0+250.00	2.48	23.23	604.19
0+258.82	2.48	21.89	626.08
0+260.00	2.48	2.93	629.01
0+270.00	2.48	24.82	653.82
0+270.82	2.48	2.03	655.86
0+280.00	2.48	22.78	678.64
0+282.82	2.48	7.00	685.64
0+282.82	2.48	0.01	685.64
0+300.00	2.48	42.63	728.27
0+320.00	2.48	49.63	777.90
0+322.57	2.48	6.38	784.29
0+334.57	2.48	29.76	814.05
0+340.00	2.49	13.49	827.53
0+346.57	2.50	16.41	843.95
0+350.57	2.52	10.04	853.99
0+358.57	2.53	20.20	874.18
0+360.00	2.54	3.62	877.80
0+370.00	2.54	25.35	903.15

Material Table			
Station	Area	Volume	Cumulative Volume
0+380.00	2.53	25.35	928.50
0+390.00	2.53	25.35	953.84
0+400.00	2.53	25.35	979.19
0+410.00	2.53	25.35	1004.54
0+411.02	2.53	2.59	1007.13
0+420.00	2.53	22.76	1029.88
0+430.00	2.53	25.35	1055.23
0+440.00	2.53	25.35	1080.58
0+450.00	2.53	25.35	1105.92
0+460.00	2.53	25.35	1131.27
0+463.47	2.53	8.80	1140.07
0+470.00	2.52	16.49	1156.56
0+471.47	2.52	3.70	1160.26
0+475.47	2.50	10.04	1170.31
0+480.00	2.49	11.32	1181.63
0+487.47	2.48	18.58	1200.21
0+499.47	2.48	29.76	1229.97
0+500.00	2.48	1.31	1231.28
0+520.00	2.48	49.63	1280.91
0+540.00	2.48	49.63	1330.54
0+560.00	2.48	49.63	1380.18
0+580.00	2.48	49.63	1429.81
0+600.00	2.48	49.63	1479.44
0+620.00	2.48	49.63	1529.08
0+640.00	2.18	46.58	1575.66
0+660.00	2.18	43.53	1619.19
0+680.00	2.48	46.58	1665.78
0+700.00	2.48	49.63	1715.41
0+720.00	2.48	49.63	1765.04
0+740.00	2.48	49.63	1814.68
0+760.00	2.48	49.63	1864.31
0+780.00	2.48	49.63	1913.94
0+800.00	2.48	49.63	1963.58
0+820.00	2.48	49.63	2013.21
0+840.00	2.48	49.63	2062.84
0+855.81	2.48	39.24	2102.09
0+860.00	2.48	10.39	2112.48
0+867.81	2.48	19.37	2131.85
0+879.81	2.50	29.90	2161.75
0+880.00	2.51	0.47	2162.22

Material Table			
Station	Area	Volume	Cumulative Volume
0+883.81	2.52	9.57	2171.79
0+890.00	2.53	15.60	2187.39
0+891.81	2.53	4.59	2191.99
0+900.00	2.53	20.75	2212.74
0+910.00	2.53	25.35	2238.08
0+920.00	2.53	25.35	2263.43
0+930.00	2.53	25.35	2288.78
0+939.43	2.53	23.90	2312.67
0+940.00	2.53	1.45	2314.12
0+950.00	2.53	25.35	2339.47
0+960.00	2.53	25.35	2364.81
0+970.00	2.53	25.35	2390.16
0+980.00	2.53	25.35	2415.51
0+987.04	2.53	17.85	2433.36
0+990.00	2.53	7.49	2440.84
0+995.04	2.52	12.71	2453.55
0+999.04	2.50	10.04	2463.59
1+000.00	2.50	2.40	2465.99
1+011.04	2.48	27.50	2493.49
1+020.00	2.48	22.21	2515.71
1+023.04	2.48	7.55	2523.25
1+040.00	2.48	42.09	2565.34
1+060.00	2.48	49.63	2614.97
1+080.00	2.48	49.60	2664.58
1+097.43	2.52	43.53	2708.11
1+100.00	2.52	6.46	2714.57
1+110.00	2.53	25.28	2739.85
1+120.00	2.53	25.35	2765.19
1+130.00	2.54	25.35	2790.54
1+140.00	2.24	23.83	2814.37
1+150.00	2.24	22.32	2836.69
1+160.00	2.24	22.32	2859.01
1+170.00	2.24	22.32	2881.33
1+180.00	2.54	23.83	2905.16
1+184.69	2.54	11.90	2917.06
1+190.00	2.54	13.45	2930.51
1+200.00	2.54	25.35	2955.86
1+210.00	2.53	25.35	2981.20
1+220.00	2.54	25.35	3006.55
1+230.00	2.53	25.35	3031.90

Material Table			
Station	Area	Volume	Cumulative Volume
1+240.00	2.53	25.35	3057.25
1+250.00	2.54	25.35	3082.59
1+260.00	2.54	25.35	3107.94
1+270.00	2.52	25.27	3133.21
1+271.95	2.52	4.92	3138.13
1+280.00	2.50	20.16	3158.29
1+300.00	2.48	49.78	3208.07
1+320.00	2.48	49.63	3257.70
1+340.00	2.48	49.63	3307.33
1+360.00	2.48	49.63	3356.97
1+380.00	2.48	49.63	3406.60
1+400.00	2.48	49.63	3456.23
1+420.00	2.48	49.63	3505.87
1+440.00	2.48	49.63	3555.50
1+460.00	2.48	49.63	3605.13
1+480.00	2.48	49.63	3654.77
1+500.00	2.48	49.63	3704.40
1+520.00	2.48	49.63	3754.03
1+540.00	2.48	49.63	3803.67
1+560.00	2.03	45.07	3848.73
1+580.00	2.03	40.50	3889.23
1+600.00	2.48	45.07	3934.30
1+620.00	2.48	49.63	3983.93
1+640.00	2.48	49.63	4033.57
1+660.00	2.48	49.63	4083.20
1+680.00	2.48	49.63	4132.83
1+700.00	2.48	49.63	4182.47
1+720.00	2.48	49.63	4232.10
1+740.00	2.48	49.63	4281.73
1+760.00	2.48	49.63	4331.37
1+780.00	2.48	49.63	4381.00
1+800.00	2.48	49.63	4430.63
1+820.00	2.48	49.63	4480.27
1+840.00	2.48	49.63	4529.90
1+860.00	2.48	49.63	4579.53
1+880.00	2.48	49.63	4629.17
1+889.51	2.48	23.61	4652.77

NOTES :
1. ALL STATIONS, COORDINATES AND LEVELS ARE IN METERS.
2. ALL OTHER DIMENSIONS ARE IN CM UNLESS OTHERWISE NOTED.
3. COORDINATES AND ELEVATIONS REFER TO THE PALESTINAN GRID SYSTEM.

LEGEND FOR PLAN

- NATURAL GROUND LEVEL
- PROPOSED GROUND LEVEL
- SUB-GRADE LEVEL

Done by:
Hussain Abu-Saada
Anan Abu-lail
Waseem Al-shalaldeh

Supervisor
Eng.Musab Shahin

Project Name
Al-majoor street

Project Name

Drawing Title
CROSS SECTION

Designed		Scale H 1:100 V 1:100
Checked		
Date	Apr. 2018	S-24